



**DESIGN & CONSTRUCTION GROUP
THE GOVERNOR NELSON A. ROCKEFELLER
EMPIRE STATE PLAZA
ALBANY, NY 12242**

ADDENDUM NO. 3 TO PROJECT NO. 45832

**CONSTRUCTION, ELEVATOR, HVAC, PLUMBING, AND ELECTRICAL WORK
REHABILITATE ELEVATORS
CULTURAL EDUCATION CENTER
EMPIRE STATE PLAZA
ALBANY, NY**

April 24, 2024

NOTE: This Addendum forms a part of the Contract Documents. Insert it in the Project Manual. Acknowledge receipt of this Addendum in the space provided on the Bid Form.

CHANGES TO ADDENDUM NO. 2

1. Item 5: SECTION 083344 – 3, Paragraph 2.02.A.1: Change paragraph to Read:
“1. Basis of Design Product: Model 2100E Fire + Smoke with Egress, by Smoke Guard, a CSW Industrials Company.”
2. Item 9: Drawing No. A-401:
 - a. Drawings Notes: Change Note 68 to Read:
“68. PROVIDE OVERHEAD COILING FIRE CURTAIN ASSEMBLY, TYPICAL AT EACH SHAFT ENTRANCE, (TYPICAL OF 7), COORDINATE INSTALLATION AND LOCATION WITH ELEVATOR AND ELECTRICAL CONTRACT FOR RELATED WORK – CLEAR OPENING WIDTH FOR HOISTWAYS 1, 2, 3, 4, 5, & 9 IS +/- 48-INCHES – CLEAR OPENING WIDTH FOR HOISTWAY 8 IS +/-60 INCHES – CLEAR OPENING HEIGHT FOR ALL HOISTWAYS IS 82 INCHES - CONTRACTOR TO VERIFY ALL DIMENSIONS IN THE FIELD”

BIDDING REQUIREMENTS – COMMON DOCUMENTS

3. DOCUMENT 001114 ADVERTISEMENT FOR BIDS: The last date for receipt of bids is changed from 2:00p.m. May 1, 2024, to 2:00p.m. May 8, 2024.

CONSTRUCTION WORK DRAWINGS

4. Drawing No. A-501:
 - a. Door Schedule Marks SB-12, SB-13, and SB-14: Delete Frame Type "M1"
 - b. Door Schedule Marks SB-12, SB-13, and SB-14: Replace Jamb Detail “4/A-502” or “5/A-502” with “4/A-501”

- c. Door Schedule Marks SB-01 and SB-02: Add the following perimeter smoke rated gasketing or approved equal:
 - i. Perimeter jamb and Head, B.O.D.: PEMKO 290_V, Finish: D.
 - ii. Surface Plate Rubber Door Sweep, B.O.D PEMKO 307_V, Finish D.

ELEVATOR WORK DRAWINGS

- 5. Drawing No. U-503:
 - a. Detail 3 Temporary Partition Plan: Change the leader note for the access door to Read: “36" X 84" HOLLOW METAL ACCESS DOOR AND FRAME SELF-CLOSING AND SELF-LOCKING – TYPICAL AT EACH PASSENGER ELEVATOR LANDING – (2)36" X 84" HOLLOW METAL ACCESS DOOR AND FRAME SELF-CLOSING AND SELFLOCKING WITH PEMKO 375 OR EQUAL OVERLAPPING ASTRAGAL – TYPICAL AT EACH FREIGHT ELEVATOR LANDING”

ELECTRICAL WORK DRAWINGS

- 6. Drawing E-103:
 - a. Detail 1 Overall Fifth Floor Plan (Hoistways Typical at Floors 6-11): Conveyor #1 Room and Conveyor #2 Room: Add luminaire Type “D” to the luminaire symbol within each room.

END OF ADDENDUM

Brady Sherlock, P.E.
Director, Division of Design
Design & Construction