



**DESIGN & CONSTRUCTION GROUP  
THE GOVERNOR NELSON A. ROCKEFELLER  
EMPIRE STATE PLAZA  
ALBANY, NY 12242**

---

**ADDENDUM NO. 1 TO PROJECT NO. 46174**

**CONSTRUCTION AND ELECTRICAL WORK  
REPLACE ROOF & WINDOWS  
DOT REGION 5, ERIE COUNTY  
3754 LAKEVIEW ROAD  
HAMBURG, NY**

June 7, 2024

**NOTE:** This Addendum forms a part of the Contract Documents. Insert it in the Project Manual. Acknowledge receipt of this Addendum in the space provided on the Bid Form.

**CONSTRUCTION WORK SPECIFICATIONS**

1. Page 028433 – 8, Article 3.07:
  - a. CHANGE Paragraph A. to Read:
    - “A. Properly containerized waste must be transported by a licensed hauler and shipped to an approved facility in accordance with 40 CFR Part 761.62 for PCB bulk product waste (caulk and adjacent masonry) and 40 CFR Part 761.61 for PCB remediation waste (poly, PPE). Waste manifests must show chain of custody. Provide one copy of each fully executed waste manifest to the Owner.”
  - b. ADD Paragraph D to Read:
    - “D. Waste shall not be stored on site in exceedance of 45 days.”

**END OF ADDENDUM**

Brady M. Sherlock, P.E.  
Director, Division of Design  
Design & Construction