



# Office of General Services

DESIGN & CONSTRUCTION GROUP  
THE GOVERNOR NELSON A. ROCKEFELLER  
EMPIRE STATE PLAZA  
ALBANY, NY 12242

---

## ADDENDUM NO. 4 TO PROJECT NO. 47082

### CONSTRUCTION AND ELECTRICAL WORK REHABILITATE WATER FILTRATION PLANT ADIRONDACK CORRECTIONAL FACILITY 196 RAY BROOK ROAD RAY BROOK, NY

March 16, 2026

**NOTE:** This Addendum forms a part of the Contract Documents. Insert it in the Project Manual. Acknowledge receipt of this Addendum in the space provided on the Bid Form.

#### BIDDING REQUIREMENTS

1. DOCUMENT 001114 ADVERTISEMENT FOR BIDS: The last date for receipt of bids is changed from Wednesday, March 18, 2026, to Wednesday, April 1, 2026.

#### ELECTRICAL WORK SPECIFICATIONS

2. SECTION 310000 EARTHWORK, Paragraph 3.22, Add the following paragraph:

“3.22 Trenchless Technologies:

- a. Trenchless technologies such as boring or horizontal directional drilling will be allowed under County roadways and in areas indicated on Contract Drawings.
- b. Provide 4-inch HDPE DR 11 casing around the 2-inch PVC electrical conduit.”
- c. A minimum of 5-ft of cover is required under the paved surface and a minimum of 36-inches of cover is required at edge of right of way.
- d. Seal casing at the ends with Polywater FST or approved equal.
- e. No concrete encasing is required in areas where trenchless technologies are employed.
- f. Adapt PVC conduit to PVC coated rigid steel conduit with watertight couplings.”

**ELECTRICAL WORK DRAWINGS**

3. Revised Drawing:
  - a. Drawing No. E-003, noted Addendum 4 dated 3/16/2026, accompanies this Addendum and supersedes the same numbered previously issued drawing.

**END OF ADDENDUM**

Brady M. Sherlock, P.E.  
Director, Division of Design  
Design & Construction

