



Office of General Services

DESIGN & CONSTRUCTION GROUP
THE GOVERNOR NELSON A. ROCKEFELLER
EMPIRE STATE PLAZA
ALBANY, NY 12242

ADDENDUM NO. 2 TO PROJECT NO. 47164

CONSTRUCTION AND ELECTRICAL WORK PROVIDE FOUNDATION REMEDIATION AND CONCRETE REPAIR CONKLINGVILLE DAM 233 COUNTY ROUTE 8 HADLEY, NEW YORK

July 31, 2026

NOTE: This Addendum forms a part of the Contract Documents. Insert it in the Project Manual. Acknowledge receipt of this Addendum in the space provided on the Bid Form.
--

BIDDING REQUIREMENTS – COMMON

1. DOCUMENT 0011114.0 ADVERTISEMENT FOR BIDS: The last date for receipt of bids is changed from Wednesday, August 19, 2026, to Wednesday, September 2, 2026.

CONSTRUCTION WORK DRAWINGS

2. Revised Drawing:
 - a. Drawing No. S-771, noted “Addendum #2”, dated 7/29/2026, accompanies this addendum and supersedes the same numbered previously issued drawing.


CONSTRUCTION WORK SPECIFICATIONS

3. SECTION 314100 DRILLING GROUT HOLES, Paragraph 2.1 B: Change paragraph to read:

“B. Grout Holes: Grout holes (primary, secondary, and tertiary) shall be drilled using the rotary core drilling method with water circulation fluid. The drill holes shall be nominally 3 inch diameter unless otherwise approved. Holes shall be thoroughly cleaned of all dust, rock chips, grease or other material which may affect water testing or grouting work. Compatible drill casing shall be provided and used if required to advance holes through unstable material and remain in the hole to be used in the grouting operations to suit the Contractor’s Work Plan. The Contractor may propose alternate methods to stabilize unstable ground such as down-stage grouting. The casing shall be advanced simultaneously with the drill bit unless otherwise approved. During the grouting work the casing shall be extracted in 5-foot increments in accordance with the Contractor’s Work Plan. Therefore, 5-foot casing lengths shall be required unless otherwise approved by the Director’s Representative.”

END OF ADDENDUM

Brady M. Sherlock, P.E.
Director, Division of Design
Design & Construction



-

DESIGN & CONSTRUCTION

CONSULTANT

CERTIFICATE OF AUTHORIZATION #: 0020747



Engineering
& Design

280 East Broad Street
Suite 200
Rochester, NY 14604
Phone: 585.232.5135
COLLIERS ENGINEERING & DESIGN CT, P.C.
www.colliersengineering.com

UNIFORM CODE STATEMENT:

TO THE BEST OF THE REGISTERED DESIGN
PROFESSIONAL'S KNOWLEDGE, BELIEF, AND PROFESSIONAL
JUDGEMENT THESE PLANS AND/OR SPECIFICATIONS ARE IN
COMPLIANCE WITH THE 2025 UNIFORM CODE.

ENERGY CODE STATEMENT:

TO THE BEST OF THE REGISTERED DESIGN
PROFESSIONAL'S KNOWLEDGE, BELIEF, AND PROFESSIONAL
JUDGEMENT THESE PLANS AND/OR SPECIFICATIONS ARE IN
COMPLIANCE WITH THE 2025 ENERGY CODE.

WARNING:

THE ALTERATION OF THIS MATERIAL IN ANY WAY, UNLESS DONE UNDER THE DIRECTION OF A COMPARABLE PROFESSIONAL, I.E. ARCHITECT FOR AN ARCHITECT, ENGINEER FOR AN ENGINEER OR LANDSCAPE ARCHITECT FOR A LANDSCAPE ARCHITECT, IS A VIOLATION OF THE NEW YORK STATE EDUCATION LAW AND/OR REGULATIONS AND IS A CLASS 'A' MISDEMEANOR.



CONTRACT: CONSTRUCTION

TITLE: PROVIDE FOUNDATION
REMEDATION AND CONCRETE
REPAIR CONKLINGVILLE DAM
NYS DAM ID #205-0415

LOCATION: 233 COUNTY ROUTE 8
HADLEY, NY
SARATOGA COUNTY

CLIENT: NYS DEPARTMENT OF ENVIRONMENTAL CONSERVATION

BID DOCUMENTS

1	07/29/2026	ADDENDUM #2 REVISED NOTE 7
0	06/22/2026	BID DOCUMENTS
MARK	DATE	DESCRIPTION

PROJECT NUMBER:	47164
--------------------	-------

DESIGNED BY:	RCP
--------------	-----

DRAWN BY:	MDI
-----------	-----

FIELD CHECK:	-
--------------	---

APPROVED: JMR

SPILLWAY REMOVALS ELEVATION & SECTIONS

DRAWING NUMBER

S-771