



Office of General Services

DESIGN & CONSTRUCTION GROUP
THE GOVERNOR NELSON A. ROCKEFELLER
EMPIRE STATE PLAZA
ALBANY, NY 12242

ADDENDUM NO. 1 TO PROJECT NO. 47573

HVAC AND ELECTRICAL WORK
REPLACE HVAC CONTROLS
BUILDING 75 & 76
INDUSTRY LIMITED SECURE CENTER
375 RUSH SCOTTSVILLE RD
RUSH, NY

March 21, 2025

NOTE: This Addendum forms a part of the Contract Documents. Insert it in the Project Manual. Acknowledge receipt of this Addendum in the space provided on the Bid Form.

ELECTRICAL WORK DRAWINGS

1. Drawing No. E-101:
 - a. KEYED NOTES, Change Note 9. to Read:

“Provide conventional carbon monoxide detector with an addressable module, and connect to existing fire alarm system. Wall mount detectors 8'-0" above finished floor. Provide wiring per manufactures recommendations. Wiring shall be routed in emt conduit. Provide all programming of existing fire alarm system as required.”

2. Drawing No. E-102:
 - a. KEYED NOTES, Change Note 9. to Read:

“Provide conventional carbon monoxide detector with an addressable module, and connect to existing fire alarm system. Wall mount detectors 8'-0" above finished floor. Provide wiring per manufactures recommendations. Wiring shall be routed in emt conduit. Provide all programming of existing fire alarm system as required.”

END OF ADDENDUM

Brady M. Sherlock, P.E.
Director, Division of Design
Design & Construction