



Office of General Services

DESIGN & CONSTRUCTION GROUP
THE GOVERNOR NELSON A. ROCKEFELLER
EMPIRE STATE PLAZA
ALBANY, NY 12242

ADDENDUM NO. 3 TO PROJECT NO. 47634

CONSTRUCTION, HVAC, PLUMBING AND ELECTRICAL WORK PROVIDE FFA BUILDING NEW YORK STATE FAIRGROUNDS 581 STATE FAIR BOULEVARD SYRACUSE, N.Y.

September 5, 2025

<p>NOTE: This Addendum forms a part of the Contract Documents. Insert it in the Project Manual. Acknowledge receipt of this Addendum in the space provided on the Bid Form.</p>
--

CONSTRUCTION WORK SPECIFICATIONS

1. Page 083325 – 2, Paragraph 2.2 B: Change Paragraph to read:

“B. Steel Section:

1. Exterior Face: Minimum .016 inch thick hot-dipped galvanized steel with horizontal embossed ribs, and factory painted with primer and polyester or acrylic finish coat; Wood grain texture; Style: Swing with Two-Piece Arched windows design.
2. Color: As selected by the Architect from door manufacturer’s standard colors.
3. Interior Face: Minimum .016 inch thick hot-dipped galvanized steel with horizontal ribs, and factory painted with primer and polyester finish coat; or minimum .016 inch thick steel with horizontal ribs, protected with an aluminum/zinc corrosion-resistant coating, with paint finish to match exterior. Stucco texture.
4. Core: Tightly packed polyurethane or polystyrene insulation. R-value to meet or exceed R-10.”

GENERAL DRAWINGS

2. Drawing No. G-004:
- a. WALL TYPES, P2: Change “PROVIDE 19/32” EXPOSURE 1 GRADE PLYWOOD SHEATHING UP TO 4’ AFF” to read “PROVIDE 19/32” EXPOSURE 1 GRADE PLYWOOD SHEATHING ABOVE 4’ AFF”

ELECTRICAL WORK DRAWINGS

3. Drawing No. E-002:

- b. General Note 10: Change “SUGGESTED DUCT BANK ROUTING SHOWN DIAGRAMMATICALLY. COORDINATE PATH WITH C-CONTRACT AND DIRECTOR’S REPRESENTATIVE PRIOR TO ROUGH-IN. ALL TRENCHING, BACKFILLING, ETC. UP TO 5’ FROM BUILDING TO BE PROVIDED BY C-CONTRACT. E-CONTRACT TO PROVIDE FROM 5’ FROM BUILDING TO BUILDING INTERIOR. COORDINATE WITH C-CONTRACT.” to read:

“SUGGESTED DUCT BANK ROUTING SHOWN DIAGRAMMATICALLY. COORDINATE PATH WITH C-CONTRACT AND DIRECTOR’S REPRESENTATIVE PRIOR TO ROUGH-IN. ALL TRENCHING, BACKFILLING, ETC. TO BE PROVIDED BY C-CONTRACT EXCEPT AS NOTED. COORDINATE WITH C-CONTRACT.”

END OF ADDENDUM

Brady M. Sherlock, P.E.
Director, Division of Design
Design & Construction