



Office of General Services

DESIGN & CONSTRUCTION GROUP
THE GOVERNOR NELSON A. ROCKEFELLER
EMPIRE STATE PLAZA
ALBANY, NY 12242

ADDENDUM NO. 2 TO PROJECT NO. 47714

CONSTRUCTION WORK ROOF REPLACEMENT 2317 GREENE ST. DOT REGION 7 ST. LAWRENCE COUNTY OGDENSBURG, NY

March 21, 2025

NOTE: This Addendum forms a part of the Contract Documents. Insert it in the Project Manual. Acknowledge receipt of this Addendum in the space provided on the Bid Form.

CONSTRUCTION WORK DRAWINGS

1. Drawing No. G-003:
 - a. LEAD-BASED AWARENESS NOTES, Add the following statements:
 - “1. All Work Activities Associated With The Disturbance Of Lead-Based Paint And Lead-Containing Materials Shall Be Completed As Defined In The Contract Documents.
 2. Xray Fluorescence Testing Has Identified Lead-Based Paint And Lead-Containing Material On Surfaces That Will Be Disturbed During The Renovation Work. Disturbance Includes Removal Of Wood Tongue And Groove Roof Decking. Lead Based Paint Or Lead Containing Paint Is Presumed To Be Present On Exterior Stucco And Untested Surfaces That May Be Disturbed Or Removed.
 3. Lead Disturbance Work Shall Be Performed In Accordance With All Applicable Federal, State And Local Regulations, Codes And Standards Including, But Not Limited To, Osha Lead In Construction 1926.62, And Specification Section 028304.
 4. Lead Disturbance Work Will Be Coordinated With Other Construction Activity.
 5. The Contractor Is Responsible For The Removal And Disposal Of Lead-Based Paint, Lead-Containing Materials And Materials Coated With Lead-Containing Paint As Indicated In The Project Specifications And Drawings. The Contractor Shall Verify Field Conditions, Measurements And Quantities. Report Any Discrepancies To The Consultant In Writing.”

2. Drawing No. A-100:
 - a. REMOVAL NOTES, Add the following statement to Note 5:

“Existing roof system is comprised of EPDM membrane adhered to insulation boards, over built-up moisture barrier, over dens deck type board over paper and tar over existing wood decking. Insulation boards are mechanically fastened to the existing wood decking. Cross reference photographs on Drawing No. 102.”

END OF ADDENDUM

Brady M. Sherlock, P.E.
Director, Division of Design
Design & Construction