



# Office of General Services

DESIGN & CONSTRUCTION GROUP  
THE GOVERNOR NELSON A. ROCKEFELLER  
EMPIRE STATE PLAZA  
ALBANY, NY 12242

---

## ADDENDUM NO. 2 TO PROJECT NO. M3172

CONSTRUCTION AND HVAC WORK  
REPLACE ROOF, BUILDING 101  
MID-STATE CORRECTIONAL FACILITY  
9005 OLD RIVER ROAD  
MARCY, NY

October 15, 2024

**NOTE:** This Addendum forms a part of the Contract Documents. Insert it in the Project Manual. Acknowledge receipt of this Addendum in the space provided on the Bid Form.

### BIDDING REQUIREMENTS – COMMON DOCUMENTS

1. DOCUMENT 001114 ADVERTISEMENT FOR BIDS: The last date for receipt of bids is changed from Wednesday, October 16, 2024, to Wednesday, October 23, 2024.

### CONSTRUCTION WORK SPECIFICATIONS

2. SECTION 075323 ADHERED EPDM ROOFING SYSTEM, Page 075323-1, Article 1.2: Remove references to "with a fleece backing."
3. Page 075323-1, Article 1.2 A.: Change Paragraph to read:  

“A. Fully Adhered EPDM System (Type-1): Smooth surfaced black 90-mil thick non-reinforced EPDM (Ethylene Propylene Diene Terpolymer) membrane fully adhered. A glass faced gypsum coverboard fully adhered over a minimum of two (2) layers of fully adhered polyisocyanurate insulation over a self-adhered vapor retarder to the existing concrete roof deck.”
4. Page 075323-1, Article 1.2 B.: Change Paragraph to read:  

“B. Revise sub paragraph B to read: "Fully Adhered EPDM System (Type-2): Smooth surfaced black 90-mil thick non-reinforced EPDM (Ethylene Propylene Diene Terpolymer) membrane fully adhered. A glass faced gypsum coverboard fully adhered over a minimum of two (2) layers of fully adhered polyisocyanurate insulation over a self-adhered vapor retarder to a glass faced gypsum underlayment board mechanically attached to the existing metal roof deck.”

5. Page 075232-8, Article 1.7 B-1.: Change Paragraph to read:

“1. Wind Speed: Up to 90mph, exposure category B (measured from the nearest NOAA weather station at 33 feet).”

**END OF ADDENDUM**

Brady M. Sherlock, P.E.  
Director, Division of Design  
Design & Construction