

**DESIGN & CONSTRUCTION GROUP  
THE GOVERNOR NELSON A. ROCKEFELLER  
EMPIRE STATE PLAZA  
ALBANY, NY 12242**

---

**ADDENDUM NO. 1 TO PROJECT NO. Q1833**

**HVAC AND ELECTRICAL WORK  
REPLACE HVAC SYSTEM, BUILDING 502  
CAMP SMITH TRAINING SITE  
11 BEAR MOUNTAIN BRIDGE ROAD  
CORTLANDT MANOR, NY**

June 16, 2023

<p><b>NOTE:</b> This Addendum forms a part of the Contract Documents. Insert it in the Project Manual. Acknowledge receipt of this Addendum in the space provided on the Bid Form.</p>
--

**GENERAL REQUIREMENTS – COMMON DOCUMENT**

1. Page 011000 - 3, Paragraph 1.09, K: DELETE the last sentence that reads “Provide temporary services required to maintain building services at all times other than during scheduled interruptions.”

**ELECTRICAL WORK**

2. Page 099102 - 8, Subparagraph 3.03, B, 1: CHANGE this paragraph to Read:
  - “1. Paint Type IAL-3: Exposed raceways, fittings, pull boxes, junction boxes, etc. in the RTI Gym 1033 and Boiler Room 1018. “

**ELECTRICAL DRAWINGS**

3. Drawing No. E-001:
  - a. Drawing Notation: CHANGE “ETN EXISTING EQUIPMENT TO BE REMOVED AND REPLACED IN KIND BY H-CONTRACT” to “ETN EXISTING EQUIPMENT TO BE REMOVED AND REPLACED IN KIND BY E-CONTRACT”.
4. Drawing No. E-101:
  - a. General Removal Notes, ADD Note 3 to Read:
    - “3. 45 kVA Transformer (ETR) is located adjacent to Panel PP-3 (plan west) in Utility Room 1038. 30 kVA Transformer (ETR) is located adjacent to Panel PP-2 (plan south) in Check Out QA/QC Room 1024.”

5. Drawing E-102:
  - a. General Notes, Add Note 11 to Read:
    - “11. 45 kVA Transformer (ETR) is located adjacent to Panel PP-3 (plan west) in Utility Room 1038. 30 kVA Transformer (ETR) is located adjacent to Panel PP-2 (plan south) in Check Out QA/QC Room 1024.”

**END OF ADDENDUM**

Brady M. Sherlock, P.E.  
Director, Division of Design  
Design & Construction