



Office of General Services

DESIGN & CONSTRUCTION GROUP
THE GOVERNOR NELSON A. ROCKEFELLER
EMPIRE STATE PLAZA
ALBANY, NY 12242

ADDENDUM NO. 2 TO PROJECT NO. Q1863

CONSTRUCTION WORK REMOVE GENERATOR & RESTORE SITE PERRY B. DURYEA STATE OFFICE BUILDING 250 VETERANS HWY HAUPPAUGE, NY 11788-5500

February 28, 2025

NOTE: This Addendum forms a part of the Contract Documents. Insert it in the Project Manual. Acknowledge receipt of this Addendum in the space provided on the Bid Form.

DRAWINGS

1. Drawing No. MD-101:
 - a. REMOVAL CODED NOTES Column, Change Note 7. to Read:

“7. Remove all concrete housekeeping pads associated with the existing Cogen unit, the previously removed fuel cell unit, and the previously removed cooling module, assume the pads are 12 inches thick and are to be fully removed. The Cogen circulating pump pad located inside the Boiler Building is assumed to be 12 inches thick and is to be fully removed and have the floor repaired to match adjacent surfaces.”
 - b. GENERAL NOTES Column, Change Note 4. to Read:

“4. Remove existing metal walkway grating above existing piping in its entirety, assume there are no under slab footings directly related to the Metal Walkway. For drawing clarity, portion of the walkway removals has been omitted. Full Extent of removal is noted on dwg and to be field verified.”

END OF ADDENDUM

Brady Sherlock, P.E.
Director, Division of Design
Design & Construction