



Office of General Services

DESIGN & CONSTRUCTION GROUP
THE GOVERNOR NELSON A. ROCKEFELLER
EMPIRE STATE PLAZA
ALBANY, NY 12242

ADDENDUM NO. 2 TO PROJECT NO. Q1891

HVAC AND ELECTRICAL WORK PROVIDE ELECTRICAL UPGRADES & BACK UP GENERATOR WILLARD DRUG TREATMENT CENTER 7116 COUNTY ROAD 132 WILLARD, NY

December 5, 2025

<p>NOTE: This Addendum forms a part of the Contract Documents. Insert it in the Project Manual. Acknowledge receipt of this Addendum in the space provided on the Bid Form.</p>
--

ELECTRICAL WORK DRAWINGS

1. Drawing No. E-101:
 - a. PLAN KEY NOTES Column, Change Note 7. to Read:
“7. PROVIDE CONDUCTORS IN 4" CONDUIT FROM NYSEG TRANSFORMER TO EXISTING SERVICE DISCONNECT. REFER TO ONE-LINE DIAGRAM ON E601. ALSO PROVIDE (3) #2 ALUMINUM UNDERGROUND ELECTRICAL 15KV FEEDERS CABLES AND (1) #2 COPPER NEUTRAL IN 4" CONDUIT FROM POLE TO TRANSFORMER IN ACCORDANCE WITH NYSEG SP-1099/SP-1294 REQUIREMENTS. - ASSUME DISTANCE OF 40FT, TERMINATIONS BY NYSEG.”
2. Drawing No. E-102:
 - a. PLAN KEY NOTES Column, Change Note 1. to Read:
“1. PROVIDE HAND HOLE FOR FUTURE CONNECTION TO UTILITY SERVICE. PROVIDE (2) 4" CONDUITS FROM HAND HOLE TO ATS. REFER TO DETAIL #4 ON E-002.”
3. Drawing No. E-103:
 - a. PLAN KEY NOTES Column, Change Note 5. to read:
“5. PROVIDE (3) #2 ALUMINUM UNDERGROUND ELECTRICAL 15KV FEEDERS CABLES AND (1) #2 COPPER NEUTRAL IN 4" CONDUIT FROM POLE TO TRANSFORMER IN ACCORDANCE WITH NYSEG SP-1099/SP-1294 REQUIREMENTS. CONNECTION WILL BE DONE BY NYSEG.”

END OF ADDENDUM

Brady M. Sherlock, P.E.
Director, Division of Design
Design & Construction

Updated 05/24/2018
Printed 12/05/2025