



**DESIGN & CONSTRUCTION GROUP  
THE GOVERNOR NELSON A. ROCKEFELLER  
EMPIRE STATE PLAZA  
ALBANY, NY 12242**

---

**ADDENDUM NO. 1 TO PROJECT NO. Q2038**

**CONSTRUCTION, HVAC, AND ELECTRICAL WORK  
RENOVATE ROOM 344, ASSEMBLY LOUNGE  
NEW YORK STATE CAPITOL  
STATE STREET  
ALBANY, NY 12224**

April 17, 2026

**NOTE:** This Addendum forms a part of the Contract Documents. Insert it in the Project Manual. Acknowledge receipt of this Addendum in the space provided on the Bid Form.

**CONSTRUCTION WORK DRAWINGS**

1. Drawing Nos. A-110, A-400, and A-503:  
Add the following note to details 1/A-110, 1/A-400, 4/A-400, and 7/A-503

“The 1’-0” radius curved surface between the horizontal Kitchen ceiling (CLG-1) and the vertical Mezzanine low wall (CLG-1) is to be constructed of (2) layers of 1/4" Gold Bon High Flex Gypsum Board (National Gypsum Company), or equivalent, installed sequentially with staggered seams, fastened to metal stud framing members spaced 6” o.c. (max) with mechanical fasteners spaced 6” o.c. (max), taped and mudded. The assembly described here should start/stop where the 1’-0” radius curved surface marries into the horizontal CLG-1 and vertical CLG-1.”

**END OF ADDENDUM**

Brady M. Sherlock, P.E.  
Director, Division of Design  
Design & Construction